



MARKETSCOPINGCHECKLIST

1. AGENCY INFORMATION

Name of Procuring Entity	GENERAL SERVICES OFFICE
End-User/Implementing Unit	GENERAL SERVICES OFFICE
Name & Designation of Representative	MARLON G. BURLAS – DIRECTOR, GENERAL SERVICES

2. PROJECT OVERVIEW

Project Name	<i>Repair and Restoration Works on Electrical Lines (Primary and Secondary Distribution Lines) and Water Supply Lines Damaged by Typhoon Tino</i>
Estimated Budget	₱ 3,640,000.00
Period of Market Scoping [From(mm/yyyy)To(mm/yyyy)]	11/2025 – 11/2025
Expected Date of Delivery (mm/yyyy)	11/2025

3. MARKET SCOPING ACTIVITY/IES CONDUCTED(Check all that apply)

This confirms that market scoping activities were conducted in accordance with Section 10 of Republic Act No. 12009 and its Implementing Rules and Regulations (IRR), and considered in the Project Procurement Management Plan, consistent with the Principle of Proportionality.

Check (✓)	Activity/ies Conducted	Documentation (as maybe applicable)
✓	Consultations with suppliers / contractors / consultants/ professional associations or industry groups	Highlights of consultations or meetings/ Proof of attendance/ Reports / Summaries/ Screenshots / Brochures / Publications/ Price quotations/ Canvassssheets/MarketAnalysis Report or similar document/s
<input type="checkbox"/>	Participation in summits, fora, or conferences	Highlights of consultations or meetings/Proof of Attendance/ Reports
✓	Review of technical, financial, or market/scientific reports	Reports / Summaries/ Screenshots / Brochures / Publications, MarketAnalysis Report or similar document/ Online Product Reviews

Check (✓)	Activity/ies Conducted	Documentation (as maybe applicable)
✓	Review of product or service brochures, marketing materials, industry journals and publications or related materials	Reports / Summaries/ Screenshots / Brochures / Publications/Online Product Reviews
✓	Price sourcing for quotations or cost estimates from suppliers, contractors, or consultants	Price quotations/Canvass sheets/ Online Product Reviews
<input type="checkbox"/>	Use of data from PhilGEPS or agency websites	Reports / Summaries/ Screenshots, Price quotations/ Canvass sheets/ PhilGEPS Postings/Online Product Reviews
<input type="checkbox"/>	Other analogous market scoping activity/ies undertaken: _____	

Notes:

- i. The market scoping activities shall be identified and undertaken at the option of the End-User or Implementing Unit based on its needs and objectives.
- ii. The list of supporting documents in the Documentation column is not exclusive and may include other documents that may be gathered by the End-User or Implementing Unit pertinent to the activity/ies conducted.


4. MARKET SCOPING RESULTS

Indicate recommendations in the column provided based on the results of the market scoping activities undertaken. These recommendations shall be considered in the development of a comprehensive and realistic PPMP, taking into account the parameters outlined under Section 10.4 of the IRR of RA12009, as may be applicable.


Parameters	Considered? (Yes/No/ Not Applicable)	Recommendations based on the Market Scoping (Attach additional documents if necessary)
a. Project Cost Estimate [Does the cost estimate align with current market prices?]	Yes	The cost estimates for electrical and plumbing materials were verified through supplier canvassing and online market sources. Prices are within the acceptable range based on 2025 market rates for steel poles, ACSR conductors, transformers, and PVC fittings. The slight difference is due to price adjustments on delivery costs and brand differences,

		also on hardware and electrical components affected by post-typhoon demand. Overall, the cost remains reasonable and within market range.
Parameters	Considered? (Yes/No/ Not Applicable)	Recommendations based on the Market Scoping <i>(Attach additional documents if necessary)</i>
b. Project Design and Specification [Does available supplier/s meet technical and financial requirements?]	Yes	The identified suppliers meet the required technical and financial capacity. Materials such as galvanized steel poles, ACSR conductors, and transformers conform to the project's technical specifications and are available locally.
c. Technical Criteria [Does the market support the proposed technical requirements?]	Yes	The market supports the proposed technical requirements for both electrical and plumbing supplies. Equivalent materials and brands are available from multiple distributors in Region VIII and nearby cities.
d. Delivery Lead Time [Are the timelines for delivery feasible?]	Yes	Local suppliers can deliver within 7–14 days after purchase order issuance. The target delivery within November 2025 is feasible given supplier stock availability.
e. Storage and Warehousing Requirements [Can the storage/warehousing needs be met considering specific conditions like temperature, humidity, and handling?]	N/A	No special storage conditions required; materials can be stored in a covered and dry facility to avoid corrosion and moisture damage.
f. Identified Risk/s [Were there any market risks identified? (e.g., limited suppliers, price volatility)]	Yes	Possible risks include limited supplier stock due to post-typhoon demand and steel price fluctuations . Recommended to proceed with early procurement and coordinate with multiple vendors to ensure timely delivery.

Prepared by:
**Personnel-in-Charge, End-User or
Implementing Unit**


ALFE MAE ANN E. MARINAY
GenSO Clerk
November 7, 2025

Approved by:
Head, End-User or Implementing Unit


MARLON G. BURLAS
Director, GenSO
November 7, 2025

DETAILED UNIT PRICE ANALYSIS					
Project Name: Repair and Restoration Works on Electrical Lines (Primary and Secondary Distribution Lines) and Water Supply Lines Damaged by Typhoon Tino					
Location: Brgy.Pangasugan ,Baybay City Leyte, VSU					
Description: Electrical and Water Lines					
ITEM #	DISCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
1	Covered Line Wire ACSR Conductor #2 AWG XLPE insulated cable 15kV Overhead(aerial installation)	meters	3000	250.00	750,000.00
2	ACSR Bare wire #2 AWG 0.6/1kV Overhead	meters	1500	80.00	120,000.00
3	ACSR insulated wire #1 AWG 0.6/1kV Overhead 210 amperes ampacity	meters	1500	180.00	270,000.00
4	Electrical Pole, Steel, Hexagonal, 25 feet, Galvanize	length	5	20,000.00	100,000.00
5	Electrical Pole, Steel, Hexagonal, 35 feet, Galvanize	length	5	40,000.00	200,000.00
6	Electrical Pole, Steel, Hexagonal, 40 feet, Galvanize	length	3	45,000.00	135,000.00
7	Electrical Pole, Steel, Hexagonal, 45 feet, Galvanize	length	2	45,000.00	90,000.00
8	Hycrimp compression tap for A Groove # 1/0-3 ACSR ,2/0 -2 STR and for B Groove 2-6 ACSR, 1-6 STR	pc	100	400.00	40,000.00
9	Hycrimp compression tap for A Groove # 1-6 ACSR , 2-8 STR and for B Groove 2-6 ACSR, 4-8 STR	pc	100	350.00	35,000.00
11	Secondary bracket (Shackle insulator) with insulator for electrical pole secondary line	set	20	400.00	8,000.00
12	15kV Steel Cross Arm Rectangular Tube Galvanized Steel 8ft	pcs	40	2,500.00	100,000.00
13	V-Brace steel (standard)	pcs	40	2,000.00	80,000.00
14	Machine bolt 5/8" x 8" galvanized with locknut and washers	set	30	250.00	7,500.00
15	Machine bolt 1/2" x 6" galvanized with locknut and washers	set	30	250.00	7,500.00
16	Galvanize round head carriage bolt 1/2" x 8" with locknut and washer	set	20	250.00	5,000.00
17	Steel Pin pole with Polymer insulator, 15KV	pcs	50	1,200.00	60,000.00
18	Quadrant dead end clamp aluminum forged 2/0	set	40	1,500.00	60,000.00
19	Dead end suspension polymer insulation 15kV	set	40	1,500.00	60,000.00

20	Angle eye thimble bolt 5/8" x 12" with locknut and washer	set	10	300.00	3,000.00
21	Angle eye thimble bolt 5/8" x 48" with locknut and washer	set	10	800.00	8,000.00
22	Guy Wire Standard 1x7 4.2Mm -10Mm Galvanized steel wire (10m/roll)	roll	7	3,000.00	21,000.00
23	Guy grip 1/7" 3 Standard Hot Dip Galvanized	pcs	20	250.00	5,000.00
24	Galvanize Guy Clamp 3 bolt	pcs	10	500.00	5,000.00
25	50 KVA single phase, Oil emersed self-cooled continual rating outdoor type transformer <ul style="list-style-type: none"> 7620 volts primary center tap ,120/240 Volts secondary, copper to copper (primary & secondary winding),bushing outdoor type, Amorphous type 	set	1	180,000.00	180,000.00
26	75 KVA single phase, Oil emersed self-cooled continual rating outdoor <ul style="list-style-type: none"> type transformer, 7620 volts primary center tap ,120/240 Volts secondary, copper to copper ,120/240 Volts secondary, copper to copper 	set	1	300,000.00	300,000.00
27	Cut-out fuse 15kV polymer insulator with Lighting arrester 15kV polymer insulator	pcs	10	12,000.00	120,000.00
28	Oval Eye bolt 5/8" x 18 with locknut and washers	set	10	500.00	5,000.00
29	Service drop wire ACSR 2 core twisted # 4 AWG 500meter/rolls	roll	2	40,000.00	80,000.00
30	Service drop wire ACSR 2 core twisted # 6 AWG 500meter/rolls	roll	2	32,000.00	64,000.00
31	U bolt parallel groove clamp aluminum 1/2	pcs	100	250.00	25,000.00
33	PVC pipe 4" with hub and gasket	length	30	4,600.00	138,000.00
34	Dresser joint 4"	pcs	30	7,350.00	220,500.00
35	Dresser joint 6"	pcs	20	12,870.00	257,400.00
36	Air release valvem 1/2"	pcs	50	1,600.00	80,000.00
	Subtotal				3,639,900.00