



Republic of the Philippines
VISAYAS STATE UNIVERSITY
Visca, Baybay City, Leyte

PURCHASE REQUEST

PPMP No. : **PPMP-2024-112624-0613**

PR No.: **STF-2024-11-03241**

Date: **11-29-2024**

Dept./Office: **PPO**

Category: **Construction
and Electrical Supplies**

Section/End-User: **Mario C. Bantugan**

Funding Source: **Special Trust Fund**

Project Title/Code: **Fire Alarm 2025**

Item #	Item Description	Unit	Qty	Unit Cost	PAR/CS	Total Cost
1	I. GENERAL REQUIREMENTS	lot	1	619,801.86		619,801.86
Specification: • Mobilization/Demobilization • Miscellaneous Expenses • Tools and equipment Rentals • Fire Code Fees						
2	II. PIPES	lot	1	2,314,221.27		2,314,221.27
Specification: • B.I. Threaded Pipes 2-1/2" x 6m, sch. 40 • B.I. Threaded Pipes 2" x 6m, sch. 40 • B.I. Threaded Pipes 1-1/2" x 6m, sch. 40 • B.I. Threaded Pipes 1" x 6m, sch. 40						
3	III. FITTINGS	lot	1	1,847,669.48		1,847,669.48
Specification: Sight Glass 1" Air Relief Valve 1" Pressure Relief Valve (set at 150 psi) Pressure Gauge Water Flow Switch 3"ø (Water Flow Sensor) Ball Valve / Butterfly Valve 2 ½"ø Ball Valve / Butterfly Valve 2"ø Check Valve 2 ½"ø Brass Check Valve 2"ø Brass Flexible Connector 2"ø						

Flange 2 ½"ø Flange 2" ø Flange 1 ½" ø G.I. Threaded Coupling Reducer 2 ½" ø x 2" ø G.I. Treaded Tee Reducer 2" ø x 1" ø G.I. Threaded Coupling Reducer 2"ø x 1 ½"ø G.I. Threaded Elbow 2 ½"ø x 90° G.I. Threaded Tee 2 ½"ø x 2 ½"ø G.I. Threaded Tee 2"ø x 2"ø G.I Threaded Elbow 2"ø x 90° G.I Threaded Elbow 1"ø x 90° G.I Threaded Tee 1"ø x 90° G.I Threaded Coupling Reducer 1"ø x ½"ø						
4	IV. ACCESSORIES	lot	1	1,219,231.04		1,219,231.04
Specification: • Sprinkler Head • Dyna Bolt ½" • Bolt and Nut ½" • 10mm Nut w/ washer • U Bolt W/ Nut • Welding Rod 6013 2.5mm • Angle Bar 3/16"x 1 ½ x 6m						
5	V. PUMP	lot	1	2,186,688.00		2,186,688.00
Specification: • Fire Pump 15 HP w/ Jockey Pump 2 HP • Control Panel for Motor Fire Pump • Control Panel for Jockey Pump						
6	VI. FIRE DEPARTMENT CONNECTION	lot	1	1,324,316.48		1,324,316.48
Specifcation: • Siamese 2" ø x 2 ½" ø x 2 ½"ø • Testing Connection 2½" ø x 2 ½" ø x 2 ½"ø • Fire Hose Cabinet w/ Complete Accessories						
7	VII. ALARM AND DETECTOR DEVICES	lot	1	2,765,824.00		2,765,824.00
Specification:						

- Smoke Detector
- Alarm Switch
- Alarm Bell
- Control Panel 1 Loop Addressable

8	VIII. ACCESSORIES	lot	1	522,000.00	522,000.00
---	-------------------	-----	---	------------	------------

Specification:

PVC Pipe - Electrical Conduit 1/2" x 3m

PVC Pipe - Electrical Conduit 3/4" x 3m

PVC Pipe - Electrical Conduit 1" x 3m

Flexible Electrical Conduit 1"

PVC Pipe - Electrical Conduit Elbow 1/2"

PVC Pipe - Electrical Conduit Elbow 3/4"

PVC Pipe - Electrical Conduit Elbow 1"

PVC Pipe - Junction Box Adapter W/Nut 1/2"

PVC Pipe - Junction Box Adapter W/Nut 3/4"

Bolt and Nut 5mm

Junction Box w/ Cover

PVC Pipe - Wall Clip



Screw With Tox 6mm

Cable Ties 5mm x 300mm

TF Wire #16 Duplex

	TOTAL				12,799,752.13
--	--------------	--	--	--	----------------------

Purpose: FIRE ALARM

Checked by:  CLINT C. SARVIDA		Funds Available:  ALICIA M. FLORES	
TWG - Construction and Electrical Supplies		HEAD, BUDGET OFFICE	
Signature:	Prepared by:  MARIO C. BANTUGAN	Noted by:  PHLOEM D. GALUPO	Approved by:  PROSE IVY G. YEPES
Printed Name:		UNIT HEAD, PROJECT LEADER	PRESIDENT, VSU
Designation:			