

SCAN HERE



PR-2023-0807-136093



Republic of the Philippines
VISAYAS STATE UNIVERSITY
 Visca, Baybay City, Leyte

PURCHASE REQUEST

PPMP No. : **32-1-607-2023-5-0-7**Dept./Office: **CVM**PR No.: **STF-2023-08-01413**Date: **08-07-2023**Section/End-User: **Joel M. Israel**Category: **Office Equipment**Funding Source: **Special Trust Fund**Project Title/Code: **CVM Laboratory shares**

Item #	Item Description	Unit	Qty	Unit Cost	PAR/ICS	Total Cost
1	Air Condition, Window Type, Inverter 1.5 HP (Manual), Standard size	pc	2	40,000.00		80,000.00

Specification:

- Cooling capacity at least 12,000 kilo joules
- EER at least 9.5
- With three speed cooling control and timer

2	Aircon Split Type 2.5 HP Inverter , With Installation	unit	2	58,000.00		116,000.00
---	--	------	---	-----------	--	------------

Specification:






- Capacity: 2.5HP
- Power Supply: 220,230,60,1 V, Hz, Ph
- Cooling Capacity: 24,000 Btu/h
- Cooling Input: 2,000W
- Cooling Current: 8.7A
- EER: 12.7

Indoor Unit

- Air Flow (Hi/Mi/Lo): 1063x955x759 m3/h
- Noise Level (Hi/Mi?Lo): 50/-/40 dB (A)
- Unit Dimension (W*D*H) : 1080x336x326mm (Indoor Unit)
- Weight (Net/Gross) 13.7/17.4 kg

Outdoor Unit

- Refrigerant Type: R32/1120
- Compressor Type: Rotary
- Unit Dimension (W*D*H) : 845x363x702mm (outdoor unit)
- Weight (Net/Gross): 49.1/52.4kg
- Application Area: 29-43sqm
- One (1) year warranty on parts and service five (5) years on compressor provided that the unit is installed by accredited installation team

TOTAL					196,000.00
Purpose: for College use					
Checked by:			Funds Available:		
 LEO A. MAMOLO			 ALICIA M. FLORES FF 08 HEAD, BUDGET OFFICE		
TWG - Office Equipment					
Signature:	Requested by:	Noted by:		Approved by:	
	 JOEL M. ISRAEL	 SANTIAGO T. PEÑA JR.		 EDGARDO E. TULIN	
Designation:	END USER	UNIT HEAD, PROJECT LEADER		PRESIDENT, VSU	